

X-band activities at FERMI FEL project in Trieste





***Gerardo D'Auria
Sincrotrone Trieste***

LBL 15-06-2012

- The FERMI@Elettra FEL project
- *X-band linearizer*
- *RF power source:*
 - *HV modulator*
 - *XL5 klystron*
 - *Accelerating structure and WG system*
- *Preliminary beam tests*
- *Outlook and conclusions*




<i>Parameter</i>	<i>FEL1</i>	<i>FEL2</i>
Wavelength (nm)	80-20	20-4
Electron beam energy (GeV)	1.2	1.5
Bunch charge (nC)	800	
Bunch length FWHM (fs)	500	
Peak current (A)	800	
Normalized emittance slice (μ rad)	≤ 1.2	≤ 1.0
Energy spread slice (KeV)	≤ 250	≤ 150
Repetition rate (Hz)	10-50	




- *When the X-band program started, none of the components of the system were commercially available.*
- *For this reason a program for their development was activated and a three years grant from Regione Friuli Venezia Giulia was awarded (2009 – 2011, now extended up to 2013).*
- *To address the very challenging tasks, we decided to set up three important collaborations with external institutes:*
 - *On Feb. 19th 2009, together with CERN and PSI, a MoU with SLAC, for the construction of five X-band klystrons (scaled at European frequency of 11.992 GHz), was signed. Two klystrons for Elettra, two for PSI and one for CERN.*
 - *On Nov. 17th 2009, we have activated a collaboration with PSI for the construction of four X-band structures.*
 - *For the high power WG components and for the construction of the structures, we decided to join the CLIC Collaboration (Compact Linear Collider) at CERN (MoU signed on April 30th 2010).*
- *For the HV modulator we decided to adopt an internal solution based on the PFN technology.*

- *Modulator completion and tests* *July '11*
- *First XL5 klystron at Elettra* *August '11*
- *Klystron installation and tests (diode)* *Sept. '11*
- *Accelerating structure and WG installations* *Oct. '11*
- *XL5 activation and tests with RF* *Nov.-Dec. '11*
- *XL5 gain curves verification (with SLAC)* *Jan. '12*
- *RF power connection to accel. structure* *Jan. '12*
- *RF conditioning (structure and WG system)* *Febr. '12*
- *Preliminary beam tests* *Febr.-March '12*
- *LLRF improvements and second test phase* *May '12*




**Classic scheme based on
PFN and Thyatron,
in house assembled**





XL5-1B Operation data

In diode mode at 50 Hz p.r.r.									With 300 nsec RF	
				Calorimetric measurements		V and I integrals				
Charging voltage	Anodic voltage	Anodic current	Micro perveance	Body power	Collector power	Collector power	Beam losses	Transm. effic.	Input RF power	Output RF power
$V_{fug}(KV)$	$V_k(KV)$	$I_k(A)$	(μP)	$B_p(W)$	$C_p(KW)$	$C_p(KW)$	$B_L(\%)$	$\eta(\%)$	$RF_{in}(W)$	$RF_{out}(MW)$
33.3	350	245	1.18	83	8.40	8.37	0.98	99.02	571	9.1
34.5	360	259	1.20	79	9.00	9.23	0.88	99.12	571	12.1
35.7	370	267	1.19	91	9.64	9.87	0.95	99.05	571	15.7
36.8	380	278	1.19	98	10.22	10.58	0.96	99.04	571	19.5
38.0	390	289	1.19	89	10.86	10.99	0.82	99.18	571	24.3
39.2	400	300	1.19	93	11.61	11.57	0.80	99.20	571	29.2
40.4	410	311	1.18	100	12.29	12.03	0.81	99.19	571	34.5
Filament hours (total)			2781	<div>← Data up to April 2012</div>						
HV hours			1373							
Diode			232							
RF (WG loads)			678							
RF (section and WG circuit)			463							



Calorimetric measurements






*RF design done by
R. Zennaro, M. Dehler, PSI*


<i>Parameter</i>	<i>Value</i>	<i>Units</i>
Structure type	$5/6 \pi$, CG	
Working frequency	11.992	GHz
Overall length	0.965	m
Active length	0.750	m
Iris diameter (average)	9.1	mm
Filling time	100	ns
Pulse repetition rate	50	Hz
Max heat load @ operating gradient	300	W

Courtesy of D. Gudkov, CERN





- The accelerating structure body consists of a stack of thick cylindrical copper disks, which are machined following the RF design of the cavity geometry.
- For the final RF frequency tuning, the disks are equipped with four radial holes.
- Each special wakefield monitor disk incorporates four coupling holes and is also equipped with tuning holes.


Courtesy of D. Gudkov, CERN



Fittings and hoses



Flexible hoses
WITZENMANN





Standard fittings
LEGRIS



- Power dissipation in the structure of about 0.3 kW;
- Two parallel cooling circuits;
- 8 cooling blocks each of 394 mm long;
- Brazed directly onto the accelerating structure body;
- Standard water connectors.

Courtesy of D. Gudkov, CERN



CERN preliminary RF tests structure N° 2



***Metallographical observation..
..shows that grains are crossing the joining plane***



Bonding of 5 test disks





Courtesy of D. Gudkov, CERN

Structure vacuum bake-out at CO.ME.B. (Rome):


- ~ 350 hours
- oven pressure $\leq 10^{-8}$ torr
- $T = 650$ °C






Structure preparation




Structure at ST







**Vacuum
valve
adapter**




Courtesy of F. Peauger

**Klystron
output flange**






**Pumping ports,
mode converters and
vacuum valve
assembly**




X-band plant with vacuum insulation

Measured ϵ_x and ϵ_y as we move the beam (6.5 ps_fwhm, 350 pC) along a line from ± 1 mm in x-y, through the X-band structure (passive, no RF)








X-band OFF



X-band gain ~10 MeV




We set $V_k = 385$ kV, corresponding to X-band energy gain=20.3 MeV




Beam energy 341.2 MeV

Beam energy 321.8 MeV


Beam energy 301.9 MeV




**X-band set +20 MeV,
on crest (acceleration)
energy jitter ~500 keV (rms)**




**X-band at zero crossing,
no energy gain
energy jitter ~200 keV (rms)**




**X-band set -20 MeV,
@180 deg (deceleration)
energy jitter ~900 keV (rms)**



X-band at -19.2 MeV (@180 deg)




Without X-band




With X-band


X-band @-19 MeV




mscrccd_bc01.03
@ 300 MeV




mscrccd_tls.03
@ 1.2 GeV




mscrccd_tls.03
@ 1.2 GeV





**X-band at 19.4 MeV
beam energy 320 MeV**




**X-band in
acceleration
energy jitter
~ 0.1%**




**X-band in
acceleration
energy jitter
~ 0.1%**




**X-band at 19.4 MeV
-180°**



**X-band at 19.4 MeV
-178°**



**X-band at 19.4 MeV
-175°**



**X-band at 19.0 MeV
-180°**

From : William Fawley <wmfawley@lbl.gov>
Subject: grazie! Re: READ this --- from FERMI CR --- do you have the calibration table for K4 voltage
Date: Wed, 13 Jun 2012 21:10:51 +0200
To: Gerardo D'Auria <gerardo.dauria@elettra.trieste.it>

grazie -- *we are having pretty good success -- making ostensibly nice pulses with 700-800 A peak currents with reasonable semi-flat portions* ; we have K4 at 37 kV

enjoy the California sun (until the fog comes in!)

cheers -- Bill & Simone

Short term program

- *Full structure characterization with the beam:*
 - *find the best operating point;*
 - *more dedicated studies on the beam kick due to the RF couplers,*
 - *verify wake fields effects, etc.*

Long term program

- *Activation of the wake field monitors*

Thanks to:

The members of linac group and Fermi commissioning team, Sincrotrone Trieste.

The colleagues of CERN and PSI working on the X-band structure for the linearizer and the XL5 klystron.

F. Peauger, CEA.

J. Eichner, A. Haase, D. Sprehn, A. Vlieks, SLAC.